



Engineering and Building Services

Official Notice

6/02/23

Effective immediately, toe-nailing is not considered a mechanical connection. Any labeling of mechanical connections in truss spec sheets, lvl spec sheets, deck construction plans, and floor joist construction plans must be done with an approved hangar device from a manufacturer.

Brent Johns  
Building Official